

# PERFORMANCE RESULTS

**Molloy Precast Products Ltd.**  
Coleraine, Clara Road  
Tullamore, Co. Offaly  
Ireland

**EN 12566-1**

**„Small wastewater treatment systems for up to 50 PT“**

Part 1: Prefabricated septic tanks

Results corresponding to the Irish National Annex IS EN 12566-1

**Septic Tank NS - 4**

Material	concrete
Durability	pass
Structural behaviour (Crushing test)	pass (also wet conditions)
Watertightness (Annex A)	pass
Nominal capacity (Usable volume) (Annex A)	4 m <sup>3</sup> (4,757 l)
Hydraulic efficiency (Annex B)	99.84 %

Performance tested by:

**PIA – Prüfinstitut für Abwassertechnik GmbH**  
(PIA GmbH)  
Hergenrather Weg 30  
D-52074 Aachen

Certified according to  
ISO 9001:2008



Notified Body number: 1739



This document replaces neither the declaration  
of conformity nor the CE marking.

Prüfinstitut für Abwassertechnik GmbH  
*Elmar Lancé*  
geprüft - tested - testé

Elmar Lancé

July 2012